BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64
No:EE/YNK-D/E-PMT/08/2012-13 Daled: 13-12-2013

APPROVED TENDER SCHEDULE –'B'

Item No: 47

Name of Work: -Construction of RCC drain at Pragathi School road in Attur, ward no:03

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri K CHANNAKESHAVAMURTHY	
				Rate	Rate in Words
1	KSRRB 300-1:Earthwork excavtion by manual means in ordinary soil involving an average horizontal throw upto 2 Meters and an average lift upto 0.5m excavated surface leveled and sides neatly dressed the disposed earth to be levelled neatly after breaking of clods complete as per specifications and complete as per specifications.with all lead and lift etc complete as per specification and direction of engineer incharge of the work.	Cum	140.80	55.00	Rupees fifty five only
2	KSRB-4-1.3 : Providing and laying in position plain cement concrete of mix M 7.5 withOPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not. exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification with all lead and lift complete asper specification as per direction of Engineer incharges	Cum	26.40	4000.00	Rupees four thousand only
3	KSRB 4.2.2 : Providing and laying in position plain cement concrete of mix M20 withOPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum with superplastesisre @ 3lts conforming to IS9103-1999Reffirmed machine mixed exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls(any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour HOM of machinery, curing, complete as per specifications. Specification with all lead and lift etc complete as per specification and direction of engineer incharge of the work.	Cum	47.52	5000.00	Rupees five thousand only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri K CHANNAKESHAVAMURTHY	
				Rate	Rate in Words
4	KSRB 4.9.2:providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications. Specification with all lead and lift etc complete as per specification and direction of engineer incharge of the work.	Quintal	33.26	7100.00	Rupees seven thousand one hundred only
5	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, attached pilasters,bittresses,buttresses plinth and string course including cost of all materials, labour complete as per specifications. with all lead and lift etc complete as per specification and direction of engineer incharge of the work.	Sqm	422.40	250.00	Rupees two hundred fifty only
6	Providing and fixing 10 cm thick pre cast RCC covering slab using reinforced cement concrete M 20 mix with stone aggregate 20 mm and down size including centring shuttering reinforcement and bar bending machine mixed concrete laid in layers not exceeding 15 cm thick welicopacted cost of all materials labour curing comlete as per specification (Data Rate Approved)	Sqm	158.40	1498.00	Rupees one thousand four hundr ninety eight only
7	KSRRB M100-1 Loading and unloading of stone boulder/stone aggregates/sand/.kanker/moorum. KSRRB M100-1:Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, excluding time for haulage and return trip complete as per specifications. MORTH Chapter 1	Cum	140.80	70.00	Rupees seventy only

Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.